

TODD COUNTY WATER DISTRICT

P.S.C. KY No. 8943
Cancels P.S.C. KY No. _____

TODD COUNTY WATER DISTRICT
OF
TODD AND LOGAN COUNTIES, KENTUCKY

RATES, RULES, AND REGULATIONS FOR FURNISHING
WATER SERVICE
IN

Todd County, including the corporate limits of Allensville, and excluding the Cities of Elkton, Trenton, and Guthrie, and the areas served by their water systems. Plus the following territory in Logan County, Kentucky: Beginning at a point one mile South of the Todd and Logan County line on Highway 107; thence East 2.15 miles; thence North 4.75 miles; thence West 2.15 miles to the Todd County line; thence South 4.75 miles to the beginning point.

FILED WITH PUBLIC SERVICE COMMISSION OF
KENTUCKY

Issued August 1, 1984
Revised January 23, 1996

Effective August 10, 1984
Effective February 23, 1996

ISSUED BY: Todd County Water District

By: *Dr. George D. Brown*
Chairman

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

APR 07 1996

PURSUANT TO 807 KAR 5.011,
SECTION 9 (1)
BY: *Jordan C. Neal*
FOR THE PUBLIC SERVICE COMMISSION

TODD COUNTY WATER DISTRICT
INDEX
RULES AND REGULATIONS

<u>ITEM NO.</u>	<u>DESCRIPTION</u>	<u>PAGE NO.</u>
	Rate Schedule	1
1.	Scope	2
2.	Revisions	2
3.	Conflict	2
4.	Application for Service	3
5.	Non-Standard Service	3
6.	Point of Delivery	3
7.	Customer's Service Line	4
8.	Ownership of Mains, Services & Appurtenances	4
9.	Discontinuance of Service by District	5
10.	Billing	5
11.	Discontinuance of Service by Customer	6
12.	Reconnection Fee	6
13.	Termination or Field Collection Charge	6
14.	Special Meter Reading Charge	7
15.	Adjustment Relative to Erroneous Meter	7
16.	Meters	8
17.	Failure of Meter	8
18.	Right of Access	8
19.	Interruption of Service	9
20.	Boilers and/or Pressure Vessels	9
21.	Backflow Preventers	10
22.	Cross-Connections	10
23.	Relocation of Water Facility	10
24.	Damage to District's Water System	10
25.	Additional Load	11
26.	Notice of Trouble	11
27.	Distribution Extensions	11
28.	Complaints	12
29.	Sale of Water	12
30.	Contributions in Aid of Construction	12
31.	Taps and Connections	13
32.	Fire Protection	13
33.	Leak Adjustments to Water Bills	13
34.	Monitoring of Customer Usage	14

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

APR 27 1996

PURSUANT TO 807 KAR 5011,
SECTION 9(1)

BY: Jackson C. Neal
FOR THE PUBLIC SERVICE COMMISSION

INDEX

Page 2

<u>ITEM NO.</u>	<u>DESCRIPTION</u>	<u>PAGE NO.</u>
	Schedule of Special Charges	15
	Schedule of Special Charges (Continued)	16
35.	Contract for Water Services/Muhlenburg County Water District	17-23
36.	Resolution Establishing a Program to Protect the Public Water Supply by Controlling Backflow & Cross-Connections	24-28

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

APR 27 1996

PURSUANT TO 807 KAR 5011,
SECTION 9 (1)

BY: Gordon C. Neal
FOR THE PUBLIC SERVICE COMMISSION

FOR Todd County Water District
Community, Town or City

P.S.C. KY. NO. 2003-00088

Revised SHEET NO. 1

Todd County Water District
(Name of Utility)

CANCELLING P.S.C. KY. NO. 2000-394

Revised SHEET NO. 1

RATES AND CHARGES

MONTHLY WATER RATES

FIRST	2,000	gallons	\$ 17.90	Minimum Bill
NEXT	8,000	gallons	9.38	per 1,000 gallons
NEXT	10,000	gallons	8.35	per 1,000 gallons
NEXT	20,000	gallons	7.33	per 1,000 gallons
OVER	40,000	gallons	5.89	per 1,000 gallons

DATE OF ISSUE August 1, 2003
Month / Date / Year

DATE EFFECTIVE August 1, 2003

ISSUED BY Dr. George D. Brown
Month / Date / Year
(Signature of Officer)

TITLE Chairman

BY AUTHORITY OF ORDER OF THE PUBLIC SERVICE COMMISSION
IN CASE NO. 2003-00088 DATED 8/1/2003

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

AUG 01 2003

PURSUANT TO 807 KAR 5.011
SECTION 9(1)

BY Charles L. Ford
EXECUTIVE DIRECTOR

Todd County Water District

RULES AND REGULATIONS

This schedule of Rules and Regulations governs the furnishing of water service by the Todd County Water District hereinafter referred to as the District and applies to all service received from the District. No employee or individual commissioners of the District is permitted to make any exception to Rates, Rules or Regulations. All Rules and Regulations are to be in effect so long as they are not in conflict with Public Service Commission Rules and Regulations. The District is further subject to all Rules and Regulations of the Commission even though not contained herein.

1. Scope

This schedule of Rules and Regulations is a part of all contracts for receiving water service from the District, and applies to all service received from the District whether the service is based upon contract, agreement, signed application, or otherwise. A copy of this schedule, together with a copy of the District's schedule of Rates and Charges, shall be kept open inspection at the office of the District. These rules are promulgated under authority granted pursuant to Kentucky Revised Statutes and Administrative Regulations 807 KAR 5. The aforesaid Rules and Regulations are hereby adopted and included the same or herein written now or as may be legally changed from time to time.

2. Revisions

These Rules and Regulations may be revised, amended, supplemented, or otherwise changed from time to time by either of the two following methods:

A. By order of the Kentucky Public Service Commission upon formal application by the District, and after hearing as provided by Commission Regulations set forth in 807 KAR 5:011.

B. By issuing and filing on at least thirty (30) days notice to the Kentucky Public Service Commission and the public all proposed changes in the Rules and Regulations, as provided by Commission Regulations set forth in 807 KAR 5:011.

3. Conflict

In case of conflict between any provision of any rate schedule and the schedule of Rules and Regulations, the rate schedule shall apply. Also, should the rules contained herein conflict with the present rules in effect under 807 KAR 5 as of this date, same shall take precedence over those contained herein.

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

APR 27 1996

DATE OF ISSUE October 1, 1990DATE EFFECTIVE November 1, 1990 PURSUANT TO 807 KAR 5:011, SECTION 9(1)ISSUED BY W. Lee D. BrownP O Box 520, Elkton, KY 42220 By James A. Neal

Name of Officer, Chairman

Address

FOR THE PUBLIC SERVICE COMMISSION

P.S.C. KY No. 8943

Revised Sheet No. 3

Cancelling P.S.C. KY No. _____

Sheet No. _____

Todd County Water District

RULES AND REGULATIONS

4. Application for Service

Any person, firm, agency, or governmental entity within the current boundary of the District may request service. Said request must be in writing on a form approved by the District.

No service requested shall be granted unless the property of said applicant is adjacent and contiguous to an existing distribution main of the District. Should the applicant desire to have the existing distribution system extended to serve him, same shall be accomplished as stipulated, hereinafter.

Should the District determine that service to a requester is available, each prospective customer desiring water shall be required to execute and sign the District's application for water service before service is supplied by the District. A 5/8 x 3/4" meter shall be "the standard customer service meter" and should be installed at all points of service unless the customer provides sufficient justification for the installation of a larger meter.

The District shall provide for a standard connection (i.e., 5/8 x 3/4" meter) to a maximum distance of fifty (50) feet from the District's existing distribution main. If the distance is greater than fifty (50) feet, the customer shall be required to pay the cost of installing the main for the additional distance, as a contribution in aid of construction.

5. Non-Standard Service

Each prospective customer requiring a non-standard service (i.e., other than a 5/8 x 3/4" meter) shall present to the District sufficient justification for same.

6. Point of Delivery

The point of delivery is the point where the meter or appurtenance is located on the customer's premises. All water lines, plumbing, and equipment beyond the meter shall be installed and maintained by the customer at his own expense in a safe and efficient manner in accordance with the District's Rules and Regulations and with the regulations of the Department of Health. The District reserves the right to determine the location of the delivery point with full regard to those wishes of the prospective customer.

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

APR 07 1996

PURSUANT TO 807 KAR 5:011,
SECTION 9(1)

BY: James C. Neal
FOR THE PUBLIC SERVICE COMMISSION

DATE OF ISSUE October 1, 1990

DATE EFFECTIVE November 1, 1990

ISSUED BY George D. Brown

P O Box 520, Elkton, KY 42220

Name of Officer, Chairman

Address

Todd County Water District

RULES AND REGULATIONS

7. Customer's Service Line

All service lines beyond the metering point should be installed of material consisting of copper or PVC pipe with a rating of not less than 160 psi. The size of service line beyond the point of delivery should not be less than 3/4"; however, a larger size may be needed to provide service. If the customer's point of use is at a higher elevation than the point of delivery, the customer should consult with a reputable engineering firm to size the service line from the point of delivery. Piping on the premises of a customer must be so installed that connections are conveniently located with respect to the District lines and mains. The customer shall provide a place for metering which is unobstructed and accessible at all times. In no event should the pressure at the customer's service pipe, under normal conditions, fall below thirty (30) psig, nor shall the static pressure exceed 150 psig, as stated by 807 KAR 5:066, Section 5.

Should a prospective customer request service at a point of delivery which now, or in the future, does not provide a delivery pressure of 30 psi or his requirements, he may make provision for an individual pressure booster system. The manner of connection, location, cross-connection, protection and type is subject to approval by District. The District reserves the right to require discontinuance and disconnection should the private booster system have a detrimental effect on the District's system.

Depth of Service Line- All service lines shall be laid at a depth sufficient to prevent freezing during the coldest weather normally experienced except where services are not intended for use during freezing weather and are actually drained during such periods. Depth shall be no less than 30" in all areas.

Inspection of Service Line - In the installation of a service line, the customer shall leave the trench open and pipe uncovered until it is inspected by the State Plumbing Inspector. The District does require a copy of the State Plumbing Inspector's Plumbing Permit on file for each service before water service begins.

8. Ownership of Mains, Services, and Appurtenances

All mains, fire hydrants, valves, crossings, and other appurtenances are and shall remain the property of the District, whether installed by the District or the customer.

All service lines from main to meter with appurtenances shall be and remain the property of District, whether installed by the District or the customer.

The customer shall install, own, and maintain his service line from meter and/or point of delivery as defined herein.

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

DATE OF ISSUE January 23, 1996 DATE EFFECTIVE February 23, 1996 APR 27 1996
ISSUED BY George D. Brown P O Box 520, Elkton, KY 42220 PURSUANT TO 807 KAR 5:011,
Name of Officer, Chairman Address SECTION 9 (1)
BY: Jordan C. Neal
FOR THE PUBLIC SERVICE COMMISSION

P.S.C. KY No. 8943

Revised Sheet No. 5

Cancelling P.S.C. KY No.

Sheet No.

Todd County Water District

RULES AND REGULATIONS

9. Discontinuance of Service by District

Water service may be discontinued by the District for violation of any rule, regulation, or condition, and especially for any of the following reasons:

A. Misrepresentation in the application or contract as to the property or fixtures to be supplied or additional use to be made of water;

B. Failure to report to the District additions to the property or fixtures to be supplied or additional use to be made of water;

C. Resale of water or giving away of water;

D. Waste or misuse of water due to improper or imperfect service pipes and/or failure to keep such pipes in a suitable state of repair;

E. Tampering with meter, meter seal, service, or valves, or permitting such tampering by others;

F. Connection, Cross-connection, or permitting the same, of any separate water supply to premises which receive water from the District;

G. Non-Payment of bills;

H. When a dangerous condition is found to exist on the customers' or applicant's premises, with reference to the continuation of water service, water service shall be cut off without notice or shall be refused, provided the District shall notify the customer or applicant immediately of the reasons for the discontinuance or refusal and the corrective actions to be taken by the applicant or customer before service can be restored;

I. Connecting more than one residence or mobile home to a meter.

10. Billing

Billing and notices relating to the conduct of the business or residence will be mailed to the customer at the address listed on the user's agreement unless change of address has been filed in writing with the District; and the District shall not otherwise be responsible for delivery of any bill or notice nor will the customer be excused from payment of any bill or any performance required in said notice.

Bills for water service are payable at the office of the District on the date of issue. The due date shall be the tenth of the month of issue.

On a new tap-on, the billing for this new service shall begin at the time the District makes water available to the customer, regardless of whether the consumer is disconnected to the meter.

APR 27 1996

PURSUANT TO 807 KAR 5011,
SECTION 9(1)

DATE OF ISSUE October 1, 1990

DATE EFFECTIVE November 1, 1990

ISSUED BY George A. Brown
Name of Officer, Chairman

P O Box 520, Elkton, KY
Address

BY: [Signature]
FOR THE PUBLIC SERVICE COMMISSION

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

Todd County Water District

RULES AND REGULATIONS

All bills not paid on or before the 10th of the month shall be deemed delinquent. When a bill becomes delinquent, the District shall serve a customer a written notice of said delinquency, and of the intent of the District to discontinue service 15 days after the 10th of the month, unless such bill is paid prior to the expiration of such 15 days. If a delinquent bill is not paid within 15 days after the due date, the water supply to the customer may be discontinued without further notice; provided, however, if, prior to discontinuance of service, there is delivered to the District, or to its employee empowered to discontinue service, a written certificate signed by a physician, a registered nurse, or a public health officer that, in the opinion of the certifier, discontinuance of service will aggravate an existing illness or infirmity on the affected premises, service shall not be discontinued until the affected resident can make other living arrangements or until thirty (30) days elapse from the time of the District's receipt of said certification, whichever occurs first. A penalty of 10% of the amount of the bill owed shall be levied and payable by the customer on all bills not paid by the tenth (10th) day of the month. The penalty will be assessed only once on any bill for rendered service.

11. Discontinuance of Service by Customer

Any customer having fulfilled his contract terms and desiring to discontinue the water service to his premises for any reason must give notice of discontinuance in writing or in person, or by telephone at the business office of the District at least three (3) days prior to the date on which the customer desires to discontinue service. If such notice is not given, a customer shall remain liable for all water used and service rendered to such premises by the District until such notice is received by the District. There will be a \$100.00 reconnection fee charged to any customer whose water service has been discontinued and the water meter removed at this own request.

12. Reconnection Fee

Where the water supply to the customer has been disconnected for non-payment of delinquent bills, a charge of \$25.00 will be made for reconnection of water service, but the reconnection will not be made until all delinquent bills and other charges, if any, owed by the customer to the District have been paid.

13. Termination or Field Collection Charge

A \$25.00 termination charge may be assessed when a District representative makes a trip to the premises of a customer for the purpose of terminating service. The charge is effective

PUBLIC SERVICE COMMISSION
KENTUCKY
EFFECTIVE

DATE OF ISSUE January 23, 1996

DATE EFFECTIVE February 23, 1996

ISSUED BY Dr. George J. Brown
Name of Officer, Chairman

P O Box 520, Elkton, KY 42220

Address

PURSUANT TO 807 KAR 5011.
SECTION 9 (1)BY: James E. Neal
FOR THE PUBLIC SERVICE COMMISSION

Todd County Water District

 RULES AND REGULATIONS

will be assessed if the District representative actually terminates service or if, in the course of the trip, the customer pays the delinquent bill to avoid termination. The charge may also be made if the utility representative agrees to delay termination based on the customer's agreement to pay the delinquent bill by a specific date. The District may make a field collection charge only once in any billing period.

14. Special Meter Reading Charge

This charge will be assessed when a customer requests that a meter be reread, and the second reading shows the original reading was correct. No charge will be assessed if the original reading was incorrect. This charge may also be assessed when a customer who reads his own meter fails to read the meter for three (3) consecutive months, and it is necessary for a District representative to make a trip to read the meter. The Special Meter Reading Charge is \$15.00.

15. Adjustment Relative to Erroneous Meter

If a meter is inaccurate in excess of +/- 2%, whether upon periodic testing or upon requested testing, additional tests shall be made at once to determine the average error of the meter, and the adjustments shall be made in the customer's water bills as follows, in accordance with 807 KAR 5:006, Section 10.

a. If the result of such tests shows an average error greater than 2% fast, the customers bill for the period during which the meter error is known to have existed, shall be recomputed and the account adjusted on the basis of the test. If the period during which the meter error existed cannot be determined, then the customer's bill shall be recomputed for one-half (1/2) of the elapsed time since the last previous test, but in no event to exceed 24 months; provided however, that if time for the periodic test has overrun to the extent that 1/2 of the time elapsed since the last test exceed 24 months, the refund shall be for the 24 months specified above; plus those months exceeding the periodic test period, provided, further that such refund may be limited to the 24 month period if failure to made the periodic test was due to causes beyond the control of the District.

b. If the result of such test shows an average error greater than 2% slow, the customer's bill for the period during which the meter error is known to have existed, shall be ~~recomputed and the account adjusted on the basis of the test. If the period during which~~

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

DATE OF ISSUE January 23, 1996

DATE EFFECTIVE February 23, 1996

ISSUED BY

Name of Officer, Chairman

P O Box 520, Elkton, KY 42220

Address

APR 27 1996

PURSUANT TO 807 KAR 5:011,
SECTION 9 (1)

BY: Jordan C. Neal
FOR THE PUBLIC SERVICE COMMISSION

Todd County Water District

RULES AND REGULATIONS

the meter error existed cannot be determined, then the customer's bill shall be recomputed for one-half (1/2) of the elapsed time since the last previous test, but in no event to exceed 12 months.

c. If the result of such tests necessitates making a refund or back billing a customer, the customer shall be notified in writing of the percentage of error, fast or slow, the date(s) of testing, and the amount of charge or credit to be shown on the next bill of the customer.

16. Meters

All meters shall be installed, renewed, and maintained at the expense of the District, and the District reserves the right to determine the size and type of meter used.

It shall be the policy of the District to test each water meter pursuant to Public Service Commission Regulation 807 KAR 5:066. In addition, the District shall make a test of any meter upon written request of any customer provided such request is not made more frequently than once each twelve (12) months. The customer shall be given the opportunity of being present at such request tests. If such tests show that the meter was not more that two percent (2%) fast, the District will make a \$10.00 Meter Test Charge.

17. Failure of Meter

In the event of a failure of a water meter, consumption will be determined in accordance with 807 KAR 5:006, Section 10.

18. Right of Access

The customer shall permit the District to lay, maintain, repair, or remove such water lines as are owned by the District and located on the customer's property, with the right of ingress and egress over the customer's property. The District's duly authorized representative and/or other duly authorized employee of the State Health Department bearing proper credentials and identifications shall be permitted to enter upon all properties for the purpose of inspection, observation, measurement, sampling and testing.

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

DATE OF ISSUE October 1, 1990DATE EFFECTIVE November 1, 1990 APR 27 1996ISSUED BY R. Kevin D. Brown
Name of Officer, ChairmanP O Box 520, Elkton, KY 42220
AddressBY: Jordan C. Neal
FOR THE PUBLIC SERVICE COMMISSIONPURSUANT TO 807 KAR 5011,
SECTION 9(1)

Todd County Water District

RULES AND REGULATIONS

in accordance with the provisions of these Rules and Regulations.

The customer shall convey, or cause to be conveyed, a perpetual easement and right-of-way to the District across any property owned or controlled by the customer whenever said easement or right-of-way is necessary to enable the District to furnish water service to the customer.

19. Interruption of Service

The District will use reasonable diligence in supplying water service, but shall not be liable in the event of , or for any loss, injury, or damage to persons or property resulting from interruptions in service, excessive or inadequate water pressure, or otherwise unsatisfactory service, whether or not caused by negligence. The District does hereby explicitly state that its system is designed for rural domestic consumption and that its provision of connections for fire protection, whether by design or implication, is only for such benefit as said customer may be able to derive from such connection.

The District shall in no event be held responsible for any claim made against it by reason of the breaking of any mains or service pipes or by reason of any other interruption of the supply of water caused by the failure of machinery or stoppage for necessary repairs or other reason. No person shall be entitled to damages nor a payment refund for any interruption of service which in the opinion of the District may be deemed necessary.

The District shall make all reasonable efforts to eliminate interruption of service and when such interruptions occur will endeavor to re-establish service with the shortest possible delay. When the service is interrupted, all consumers affected by such interruptions will be notified in advance whenever it is possible to do so.

20. Boilers and/or Pressure Vessels

Customers having boilers and/or pressure vessels receiving a supply of water from the District must have a reduced pressure back-flow preventer and a check valve on the water supply line and a vacuum valve on the stream line to prevent collapse in case the water supply from the District is discontinued or interrupted for any reason, with or without notice. It is the responsibility of the customer to make provisions for protection of this equipment in case of interrupted or intermittent service.

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

APR 27 1996

DATE OF ISSUE October 1, 1990

DATE EFFECTIVE November 1, 1990

PURSUANT TO 807 KAR 5011,
SECTION 9(1)

ISSUED BY George A. Brown
Name of Officer, Chairman

P O Box 520, Elkton, KY 42220
Address

BY James C. Neal
FOR THE PUBLIC SERVICE COMMISSION

P.S.C. KY No. 8943

Revised Sheet No. 10

Cancelling P.S.C. KY No.

Sheet No.

Todd County Water District

RULES AND REGULATIONS

21. Backflow Preventers

All services shall have a means of backflow prevention, such type and location subject to approval of District.

The District's standard service shall provide said backflow prevention as a part of its service connection. Special services and fire connections shall have backflow preventers of a type approved by the District, installed at the cost of prospective customer.

22. Cross-Connections

Kentucky Department of Health, Kentucky Public Service Commission and these Rules and Regulations do hereby explicitly state that cross-connection of the District's system with any other source is hereby prohibited.

23. Relocation of Water Facility

The District may, at the request of a customer or other person, relocate, change, or modify existing District owned equipment, mains, or appurtenances. Those requesting shall reimburse District for such changes at actual cost including but not limited to appropriate legal, administrative, engineering, and overhead costs.

24. Damage to District's Water System

No person shall break, damage, destroy, uncover, deface, tamper with, or otherwise alter any structure, appurtenance, equipment, or other property which is a part of the District's water works. Any person violating this provision shall be subject to discontinuation of water service and shall pay all costs of repairing or replacing the property including but not limited to all overhead expenses.

Any person, firm, or organization working around or near the District's distribution mains, appurtenances, or other property may request the District to indicate the location of same. However, location by District of same does not relieve such person of complete responsibility and liability for any and all damages, liability, and loss to the District's property resulting from any act of such person or his assigns and/or agent.

Any damage or injury to persons or property caused by or resulting from the acts of the customer or any other individual in relation to the District's property shall be paid by the customer or other individual including but not limited to all loss, costs, and expenses including attorneys fees and court costs unless otherwise determined by a court of

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

APR 27 1996

DATE OF ISSUE October 1, 1990

DATE EFFECTIVE November 1, 1990

ISSUED BY

Name of Officer, Chairman

P O Box 520, Elkton, KY 42220

Address

BY:

SECTION 9(1)

PURSUANT TO 807 KAR 5011.

Todd County Water District

RULES AND REGULATIONS

competent jurisdiction. Said customer or other individual shall indemnify the District from all loss, cost, and expense, including but not limited to attorneys fees and court costs, resulting from or caused by the aforementioned acts.

25. Additional Load

The service connection supplied by the District for each customer has a definite capacity, and no addition to the equipment or load connected thereto shall be allowed except by consent of the District. Failure to give notice of additions or changes in load, and to obtain the District's consent for same, shall render the customer liable to the District for all loss, cost, and expense, for any damage to any of the District's lines or equipment caused by the additional or changed installation.

26. Notice of Trouble

Customer shall notify the District immediately should the service be unsatisfactory for any reason, or should there be any defects, trouble, or accidents affecting the supply of water. Such notices, if verbal, shall be confirmed in writing.

27. Distribution Extensions

The District's policy for the extension of water lines is as described following: The District will approve all extensions when the water supply is adequate and the project can be properly engineered. The financing of distribution extensions are as follows and will be offered in an undiscriminatory manner to all customers under similar conditions.

Option 1-All costs are paid by the Water District from grants or loans acquired for the project.

Option 2-The Water District will pay the cost of materials and the customers of the extension will pay the cost of installation. This option will be used as surplus funds are accumulated by the District.

Option 3-The Water District will make an extension of 50 feet or less to its existing distribution main without charge for a prospective customer who applies for service.

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

APR 07 1996

DATE OF ISSUE October 1, 1990 PURSUANT TO 807 KAR 5011, SECTION 9(1) EFFECTIVE November 1, 1990 PURSUANT TO 807 KAR 5011, SECTION 9(1)
ISSUED BY Revered Brown Jordan P.O. Box 520, Elkton, KY 42220
Name of Officer, Chairman for the PUBLIC SERVICE COMMISSION Address BY: Jordan C. Neal
FOR THE PUBLIC SERVICE COMMISSION

Todd County Water District

RULES AND REGULATIONS

Option 4-The customers on an extension longer than 50 feet per customer will pay all costs of construction above an initial cost paid by the District for 50 feet per customer, as prescribed in the Public Service Commission extension plan, pursuant to 807 KAR 5:066, Section 11.

The construction of all extensions must conform to the specifications of the District. A designated person or company shall be responsible for the proper completion of a project.

It is the Water District's responsibility to set and maintain meters on an extension for the current tap-on fee paid by each customer of \$350.00 per 5/8 x 3/4" meter. No unused meters will be set. A separate meter for each home is required.

Any person desiring an extension to the District's system shall request in writing in a form approved by the District for such extension.

Nothing contained herein shall be construed to prohibit the District from making extensions under different arrangements provided such arrangements have been approved by the Public Service Commission.

28. Complaints

Complaints may be made to the manager of the system in person or by telephone, whose decision may be appealed to the District Commissioners. Such appeal shall be in writing within ten (10) days of date of decision by manager, which shall also be in writing and dated, stating the nature of the complaint and supporting evidence. Decisions by the District's Commissioners are final subject only to appeal to the Public Service Commission according to the procedures of that body. If a complaint is not resolved, the utility will advise the complainant of his right to file a complaint with the Commission, and will provide the complainant with the address and phone number of the Commission.

29. Sale of Water

Water furnished by the District may be used for domestic consumption by the customer's household or business, subject to special service agreements. The customer shall not sell, donate, give or allow use of such water to anyone except those members of this household or his business whichever is applicable.

30. Contributions in Aid of Construction

The District will accept contributions in aid of construction including but not limited to customer financed extensions to its water system. In addition, such contributions in aid

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

DATE OF ISSUE October 1, 1990

DATE EFFECTIVE November 1, 1990 APR 27 1996

ISSUED BY George A. Brown
Name of Officer, ChairmanP O Box 520, Elkton, KY 42220
AddressPURSUANT TO 807 KAR 5-011,
SECTION 9 (1)BY: Jordan C. Neal
FOR THE PUBLIC SERVICE COMMISSION

Todd County Water District

RULES AND REGULATIONS

of construction may consist of cash donations, in any amount, which the District may, at its option, apply to expenses of an extension or other projects. The acceptance by the District of contributions in aid on construction entitles no one to a refund and none shall be made, except under the conditions set out in 807 KAR 5:066, Section 11.

31. Taps and Connections

All taps and connections to the mains of the district shall be made by and/or under the supervision and direction of District personnel or contractors.

32. Fire Protection

The District's system is not designed nor intended for use for fire protection in any manner whatsoever. Any customer using same for fire protection does so at his own full and sole responsibility and risk.

The District makes no warranty as to the sufficiency of the water supply or the adequacy of the water pressure at any time.

Fire Hydrants installed on the distribution lines of the District are for the sole purpose of flushing the lines, or other uses by the District necessary for proper maintenance of the lines. The District is not responsible for, nor does it guarantee, any minimum pressure or flow at these hydrants, other than the minimum required by the Public Service Commission for distribution lines. Fire hydrants used by fire department units in the performance of their duty, any damage to the distribution lines, resulting from excessive pumping pressure will be the liability of that unit.

Conventional fire hydrants may be installed by a utility only on 6-inch or larger water mains and only when a professional engineer with a Kentucky registration certifies that adequate and reliable fire flows can be obtained in conformance with good standard engineering practice.

33. Leak Adjustments to Water Bills

Each customer is entitled to one leak adjustment per water service. Adjustments for leaks will be figured as follows:

1. Average the last three months water usage for that customer.
2. Subtract this average usage from the actual usage during the leak.
3. Divide these gallons by 2. (The District takes a loss one-half the water loss and charges the customer for one-half.)

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

DATE OF ISSUE October 1, 1990

DATE EFFECTIVE November 1, 1990

ISSUED BY George A. Brown
Name of Officer, ChairmanP O Box 520, Elkton, KY 42220
AddressAPR 27 1986
PURSUANT TO 807 KAR 5:011,
SECTION 9 (1)
BY: Jason C. Hall
FOR THE PUBLIC SERVICE COMMISSION

RULES AND REGULATIONS

4. Add the gallons of the average usage (item 1) and the gallons of one-half the leak (item 3) and use the total to figure the adjusted bill.

34. Monitoring of Customer Usage

At least once annually the Water District will monitor the usage of each customer according to the following procedure:

1. The customer's annual usage for the most recent 12 month period will be compared with the annual usage for the 12 months immediately preceding that period.

2. If the annual usage for the two periods are substantially the same or if any difference is known to be attributed to unique circumstances, such as unusual weather conditions, common to all customers, no further review will be done.

3. If the annual usages differ by 20 percent or more and cannot be attributed to a readily identified common cause, the Water District will compare the customer's monthly records for the 12 month period with the monthly usage for the same months of the preceding year.

4. If the cause for the usage deviation cannot be determined from analysis of the customers meter reading and billing records, the Water District will contact the customer by telephone or in writing to determine whether there have been changes such as different number of household members or work staff, additional or different appliances, changes in business volume, or known leaks in the customer's service line.

5. Where the deviation is not otherwise explained, the Water District will test the customers meter to determine whether it shows an average error greater than 2 percent fast or slow.

6. The Water District will notify the customer of the investigation, its findings, and any refunds or backbilling in accordance with 807 KAR 5:006, Section 10(4) and (5).

In addition to the annual monitoring, the Water District will immediately investigate usage deviations brought to its attention as a result of on-going meter reading or billing processes or customer inquiry.

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

APR 27 1996

PURSUANT TO 807 KAR 5:011,
SECTION 9 (1)

BY: Jordan C. Neal
FOR THE PUBLIC SERVICE COMMISSION

DATE OF ISSUE April 30, 1992

DATE EFFECTIVE April 30, 1992

ISSUED BY Mr. George W. Brown

P O Box 520, Elkton, KY 42220

Name of Officer, Chairman

Address

Todd County Water District

RULES AND REGULATIONS

Summary
Schedule of Special Service Charges

The following charges for special services shall be made:

1. Discontinuance of Service by Customer Reconnection Fee. A charge of \$100.00 shall be made for all service reconnections made, after the service was voluntarily discontinued by the request of the customer.
2. Service Reconnection Fee. A charge of \$25.00 shall be made for all service reconnections made, except that there shall be no connection charges made for service on the original installation of facilities.
3. Termination or Field Collection Fee. A charge of \$25.00 shall be made for all service terminations, or field collections made. This charge will be assessed if the representative actually terminates the service or if, in the course of the trip, the customer pays the delinquent bill to avoid termination.
4. Special Meter Reading Fee. A charge of \$15.00 shall be made for meter re-reads made at the customers request, or if a customer who reads their own meter fails to read the meter for three consecutive months, and it becomes necessary for a District representative to make a trip to read the meter.
5. Meter Test Fee. Upon request and payment of \$10.00, customers may have their meter tested provided request by customer is not more frequent than once each twelve months. If such test shows the meter to be more than two percent fast, a refund of the \$10.00 charge shall be made and the bill adjusted accordingly. If the periodic testing requirement of 807 KAR 5:066 (18) has not been met for the meter tested, no charge will be made for the test regardless of the results of the test.
6. PSC Meter Test Complaint. Any customer of the District may request a meter test by written application to the Kentucky Public Service Commission and charges for this test will be as shown in 807 KAR 5:066, Section 20 and will be collected by the Public Service Commission. Such a request shall not be made more frequently on one meter than once each twelve (12) months.

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

DATE OF ISSUE January 23, 1996

DATE EFFECTIVE February 26, 1996 APR 27 1996

ISSUED BY W. George Brown
Name of Officer, ChairmanP O Box 520, Elkton, KY 42220
AddressPURSUANT TO 807 KAR 5011,
SECTION 9 (1)BY: Jordan C. Neal
FOR THE PUBLIC SERVICE COMMISSION

TODD COUNTY WATER DISTRICT

RULES AND REGULATIONS

7. Returned Check Fee. A \$10.00 charge will be levied and paid by the customer to the District on each check of the customer "returned" for whatever reason.
8. Tap-On Fees and Connections. The established tap-on or connection fee is based on the size of the installed metering equipment and is as follows:
5/8" x 3/4" Meter \$ 450.00
1" Meter Actual Cost of Installation
9. Name Change Fee. A name change fee of \$15.00 will be charged to customers when the name on an account is changed from one owner/renter to another owner/renter.

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

DEC 01 1997

PURSUANT TO 807 KAR 5.011,
SECTION 9 (1)BY: Stephan D. Bell
SECRETARY OF THE COMMISSIONDATE OF ISSUE October 31, 1997DATE EFFECTIVE December 1, 1997ISSUED BY Dr. George D. Brown
Name of Officer, ChairmanP O Box 520, Elkton, KY 42220
Address

RULES AND REGULATIONS

Item 35.

CONTRACT FOR WATER SERVICE

THIS CONTRACT is made and entered into this 29th day of June, 1993, by and between the MUHLENBERG COUNTY WATER DISTRICT, a body corporate, and the TODD COUNTY WATER DISTRICT, a body corporate.

WITNESSETH:

That whereas, the Muhlenberg County Water District and the Todd County Water District have each been organized and established under the provisions of Chapter 74 of the Kentucky Revised Statutes for the purpose of constructing and operating water supply distribution systems serving water users within their respective districts; and whereas, Muhlenberg County Water District serves a territorial area encompassing Muhlenberg County and Todd County Water District serves a territorial area encompassing Todd County and a designated portion of Logan County; and whereas, certain residents of Muhlenberg County residing in the geographical area described on the plat attached hereto and labeled "Exhibit A" (hereinafter referred to as the contract service area) desire and have need of water service; and whereas, it is presently impractical for the Muhlenberg County Water District to extend water service to Muhlenberg County residents in the contract service area from existing lines owned by the Muhlenberg County Water District due to the lack of water pressure, rocky terrain features and long distance from any existing distribution line; and whereas, it is the desire of the Muhlenberg County Water District to contract with the Todd County Water District to provide service to Muhlenberg

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

DATE OF ISSUE August 6, 1993

DATE EFFECTIVE August 6, 1993

AUG 6 1993

ISSUED BY Dr. George D. Brown
Name of Officer, ChairmanP O Box 520, Elkton, KY 42220
Address

PURSUANT TO 807 KAR 5:011.

SECTION 9 (1)

BY: Chas. H. Helle
PUBLIC SERVICE COMMISSION MANAGER

P.S.C. KY No. 8943

Original Sheet No. 18

Cancelling P.S.C. KY No. _____

Sheet No. _____

Todd County Water District

RULES AND REGULATIONS

County residents residing within the contract service area which property lies wholly within the jurisdictional limits of the Muhlenberg County Water District;

NOW, THEREFORE, for and in consideration of the mutual covenants and agreements herein contained, it is understood and agreed as follows:

1. This contract is made pursuant to the provisions of KRS 74.414, and no monetary consideration is being paid to or received by the Muhlenberg County Water District or the Todd County Water District except as specified below. Additional consideration for this contract is the general benefit which will accrue to water customers residing within the jurisdictional limits of the Muhlenberg County Water District in the specific geographical area described on the attached plat.

2. The Todd County Water District agrees to provide water service to the area described on the attached plat for and on behalf of the Muhlenberg County Water District. As compensation for the service so provided, the Muhlenberg County Water District hereby assigns to the Todd County Water District the right to receive all tap fees and payments for water service due from water customers within the contract service area. The Todd County Water District shall bill for water services directly to customers within the contract service area. The rate schedule applicable to water customers served under this contract shall be equal to the rates charged by the Todd County Water District to residents within the jurisdictional area of the Todd County Water District.

-2-

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

DATE OF ISSUE August 6, 1993

DATE EFFECTIVE August 6, 1993

AUG 6 1993

ISSUED BY Mr. Henry D. Brown
Name of Officer, Chairman

P O Box 520, Elkton, KY 42220
Address

PURSUANT TO 807 KAR 5-011,
SECTION 9 (1)

BY: Glenn Keller

P.S.C. KY No. 8943

Original Sheet No. 19

Cancelling P.S.C. KY No. _____

Todd County Water District

Sheet No. _____

RULES AND REGULATIONS

3. It is agreed and understood that all water lines, meters and equipment which were heretofore or may hereafter be located within the jurisdictional area described on the attached plat are and shall continue to be the property of the Muhlenberg County Water District, and the Todd County Water District shall acquire no ownership interest in this distribution system. The Todd County Water District shall maintain all water distribution systems and shall provide water service to customers within the contract service area in accordance with the rules and regulations of the Public Service Commission and in the same manner as provided to customers located within the territorial area of the Todd County Water District. It is understood and agreed that Muhlenberg Water District will not be responsible for any expense associated with the actual installation of water distribution mains, meters and other appurtenances within the territorial area which is the subject of this agreement.

4. It is understood and agreed that this contract is a service contract and it shall not be construed as an extension of the territorial and/or jurisdictional area of the Todd County Water District into Muhlenberg County within the meaning of KRS 74.020 or any other applicable statute or regulation.

5. This contract shall be for an initial term of five (5) years from the date of its execution, and it shall be automatically renewed for successive five year terms unless cancelled by either party in writing delivered to the other party prior to expiration of any term.

-3-

PUBLIC SERVICE COMMISSIC
OF KENTUCKY
EFFECTIVE

DATE OF ISSUE August 6, 1993

DATE EFFECTIVE August 6, 1993 AUG 6 1993

ISSUED BY George D. Brown

P O Box 520, Elkton, KY 42220

Name of Officer, Chairman

Address

PURSUANT TO 807 KAR 5.0
SECTION 9 (1)

P.S.C. KY No. 8943

Original Sheet No. 20

Cancelling P.S.C. KY No. _____

Todd County Water District

Sheet No. _____

RULES AND REGULATIONS

6. Service to the customers residing within the designated Muhlenberg County territory shall be governed according to the policies, rules, water service rates and regulations of the Todd County Water District during the period of the contract.

7. The Todd County Water District shall provide water service and water to the customers of Muhlenberg County Water District in the territorial area covered by this Agreement with such pressure and such quality as shall be required from time to time by the Public Service Commission of Kentucky. It shall hold the Muhlenberg County Water District harmless from all liability whatsoever associated with the providing of said water service during the term of this contract.

8. This contract is part of a settlement agreement arising out of a Complaint filed before the Commonwealth of Kentucky, Public Service Commission, the same being Case No. 93-070, and this contract is subject to the approval of the Public Service Commission of Kentucky.

9. The terms of this service contract shall be automatically deemed to apply to any resident of Muhlenberg County who is actually receiving direct water service or purchasing water from the Todd County Water District as of the date of execution of this contract.

This Contract shall be binding upon the successors and assigns, if any, of the Muhlenberg County Water District and the Todd County Water District.

IN WITNESS WHEREOF, the parties hereto, acting under the authority of their respective governing bodies, have caused this

-4-

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

DATE OF ISSUE August 6, 1993

DATE EFFECTIVE August 6, 1993

AUG 6 1993

ISSUED BY Dr. George A. Brown
Name of Officer, Chairman

P O Box 520, Elkton, KY 42220
Address

PURSUANT TO 807 KAR 5.011,
SECTION 9 (1)

BY: George A. Brown
PUBLIC SERVICE COMMISSION MANAGER

P.S.C. KY No. 8943

Original Sheet No. 21

Cancelling P.S.C. KY No. _____

Todd County Water District

Sheet No. _____

RULES AND REGULATIONS

Contract to be duly executed the day and date first above written.

NUHLBERG COUNTY WATER DISTRICT

By: Bobby J. Cregar
Chairman

ATTESTED:

James C. Spurlin

TODD COUNTY WATER DISTRICT

By: Dr. George D. Brown
Chairman

ATTESTED:

Bennie R. Brown

This Contract is approved on behalf of the Public Service Commission of Kentucky, this the _____ day of _____, 1993.

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

AUG 6 1993

PURSUANT TO 807 KAR 5.011,
SECTION 9 (1)

BY: George D. Brown
PUBLIC SERVICE COMMISSION MANAGER

-5-

DATE OF ISSUE August 6, 1993

DATE EFFECTIVE August 6, 1993

ISSUED BY Dr. George D. Brown
Name of Officer, Chairman

P O Box 520, Elkton, KY 42220
Address

P.S.C. KY No. 8943


Original Sheet No. 22

Cancelling P.S.C. KY No.

Todd County Water District

Sheet No.

RULES AND REGULATIONS



PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

AUG 6 1993

Exhibit "A"

PURSUANT TO 807 KAR 5.011,
SECTION 9 (1)

BY: [Signature]
PUBLIC SERVICE COMMISSION MANAGER

DATE OF ISSUE August 6, 1993

DATE EFFECTIVE August 6, 1993

ISSUED BY [Signature]
Name of Officer, Chairman

P O Box 520, Elkton, KY 42220
Address

P.S.C. KY No. 8943

Original Sheet No. 23

Cancelling P.S.C. KY No. _____

Sheet No. _____


Todd County Water District

RULES AND REGULATIONS

BOUNDARY DESCRIPTION OF APPROXIMATELY 172 ACRES OF MUHLENBURG COUNTY WHICH IS SURROUNDED ON THE WEST, NORTH, AND EAST SIDES BY LAKE MALONE, TO BE PROVIDED WITH WATER BY TODD COUNTY WATER DISTRICT ON A CONTRACTUAL BASIS FROM THE MUHLENBURG CO. WATER DISTRICT

Beginning at a point in the Water-line of Lake Malone at the Logan County-Muhlenburg County line, near the Southwest corner of Lot No. 4, Section I, Kings Cove Subdivision; thence running about S78-JUM 2650 ft with the Muhlenburg-Logan County line across a peninsula to the water-line of Lake Malone; thence about North approximately 2800 ft, Northeast approximately 1900 ft, and Southeast approximately 3800 ft with the East, South and West shorelines of Lake Malone in Muhlenburg County, around said peninsula, to the point of beginning, containing approximately 172 acres more or less as shown by the attached Topographic Map.

John N. Tinsley
JOHN N. TINSLEY
Registered Land Surveyor
State of Kentucky
License No. 2189



PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

AUG 6 1993

PURSUANT TO 807 KAR 5.011,
SECTION 9 (1)

BY: *Sharon Helle*
PUBLIC SERVICE COMMISSION MANAGER

Exhibit "A" (1)

DATE OF ISSUE August 6, 1993

DATE EFFECTIVE August 6, 1993

ISSUED BY

Dr. Roger N. Brown
Name of Officer, Chairman

P O Box 520, Elkton, KY 42220

Address

Todd County Water District

RULES AND REGULATIONS

Item 36.

A RESOLUTION ESTABLISHING A PROGRAM TO PROTECT THE PUBLIC WATER
SUPPLY BY CONTROLLING BACKFLOW AND CROSS CONNECTIONS.

WHEREAS, the Kentucky Natural Resources and Environmental Protection Cabinet has enacted administrative regulations which require every public water system to determine if or where cross connections exist and to eliminate them; and

WHEREAS, the Board Members of the Todd County Water District, hereinafter called "Water District", realize that they have a responsibility to protect the public health by providing a safe source of drinking water, and that cross connections could affect the health and economic growth of the community;

NOW THEREFORE, be it resolved by the Board Members of the Todd County Water District:

SECTION 1. TITLE. This resolution shall be known and may be cited as the "Cross Connection Resolution".

SECTION 2. PURPOSE AND AUTHORITY. (A) It is the purpose of this program to assure that the public water supply is protected from contamination due to backflow or cross connections. The Board recognizes that contamination of the public water supply presents an imminent health hazard to the residential and non-residential users of the public water system; the threat of significant economic loss due to disrupted water service to such residential and nonresidential water users and the potential liability to the Water District.

(B) It is the further purpose of this resolution to meet the requirements of 401 KAR 8:020 as enacted by the Kentucky Natural Resources and Environmental Protection Cabinet.

SECTION 3. DEFINITIONS. (A) "Air Gap" means the measured vertical distance from the lowest end of a potable water outlet to

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

APR 07 1996

PURSUANT TO 807 KAR 5.011,
SECTION 9(1)

BY: Jordan C. Neal
FOR THE PUBLIC SERVICE COMMISSION

DATE OF ISSUE January 23, 1996

DATE EFFECTIVE February 23, 1996

ISSUED BY Mr. George A. Brown

P O Box 520, Elkton, KY 42220

Name of Officer, Chairman

Address

Todd County Water District

RULES AND REGULATIONS

the flood rim or line of the fixture or receptacle into which it discharges. The minimum required air gap shall be twice the effective opening of the potable water outlet.

(B) "Approved Backflow Assembly" means any device that may be approved by the Cabinet in lieu of proper air gap separation.

(C) "Auxiliary Water Supply" means any water supply on or available to the premises other than the Water District's public water supply. These auxiliary waters may include water from any natural source such as a well, spring, river, stream or body of water or any water or other substance of unknown or questionable quality that may present a health or system hazard to the potable public water supply.

(D) "Backflow" means the reversal of the normal flow of water caused by either back pressure or back siphonage.

(E) "Back Pressure" means the flow of water or other liquids, mixtures, or substances under pressure into the distribution pipes of a potable water supply system from any source other than the original water source.

(F) "Back Siphonage" means the flow of water or other liquids, mixtures, or substances into the distribution pipes of a potable water supply system from any source other than the original water source, caused by the reduction of pressure in the potable water supply system.

(G) "Backflow Prevention Assembly" means an assembly or means designed to prevent backflow. A listing of acceptable backflow prevention assemblies and degree of hazard is available in the Kentucky State Plumbing Law, Regulations, and Code.

(H) "Contamination" means an impairment of the quality of the potable water supply by any waste product, fluid, substance, compound or other material to a degree which creates an actual or potential hazard to the public health through poisoning or through the spread of disease.

(I) "Cross Connection" means any physical connection or arrangement of piping or fixtures between two otherwise separate piping systems one of which contains potable water and the other nonpotable water or substance of questionable quality, through

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

APR 27 1996

PURSUANT TO 807 KAR 5:011,
SECTION 9(1)

BY: Jordan A. Neal
FOR THE PUBLIC SERVICE COMMISSION

DATE OF ISSUE January 23, 1996 DATE EFFECTIVE February 23, 1996

ISSUED BY Sh George St. Brown P O Box 520, Elkton, KY 42220
Name of Officer, Chairman Address

Todd County Water District

RULES AND REGULATIONS

which, or because of which, backflow may occur into the potable water system.

(J) "Cross Connection - Controlled" means a connection between a potable water system and a nonpotable water system with an approved backflow prevention assembly properly installed and maintained so that it will continuously afford the protection commensurate with the degree of hazard.

(K) "Thermal Expansion Tank" means a device installed on the cold water supply line near a water heater to compensate for the expansion of water within a water system when such water is heated.

SECTION 4. REQUIREMENTS. The Water District shall provide protection to the public water system against backflow by implementing the following requirements:

(A) "Residential" - Buildings used for habitation or occupancy shall be considered as residential buildings. No water service connection to any premises shall be installed or allowed to be installed by the Water District unless such service connection is protected by a backflow prevention assembly. Residential service connections shall be considered as low hazard applications and all such connections shall have at a minimum a dual check valve backflow preventer installed between the water meter and the residence. The Water District may require additional or alternate backflow prevention assemblies if the degree of hazard constitutes a higher level of protection for the public water system.

(B) "Non-Residential" - No water service connection to any non-residential facility shall be installed or allowed to be installed by the Water District unless such water service connection is protected by a backflow prevention assembly. The type of protective device required shall be determined at the time of installation of the service connection and shall be commensurate with the degree of hazard at the point of such service connection. At a minimum the service connection shall be installed with a dual check valve backflow preventer. In the event activities to occur within a non-residential facility change and creates a higher degree of hazard, then the backflow prevention assembly shall be

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

APR 07 1996

PURSUANT TO 807 KAR 5011,
SECTION 9 (1)

BY: Jordan C. Neal
FOR THE PUBLIC SERVICE COMMISSION

DATE OF ISSUE January 23, 1996

DATE EFFECTIVE February 23, 1996

ISSUED BY

Name of Officer, Chairman

P O Box 520, Elkton, KY 42220

Address

Todd County Water District

RULES AND REGULATIONS

replaced with an assembly which provides acceptable protection.

(C) "Inspections" - The customer's water system shall be open for inspection at all reasonable times to authorized representatives of the Water District to determine whether cross connections or other structural or sanitary hazards exist. When such a condition becomes known, the Water District may deny or immediately discontinue service to the premises by providing a physical break in the service line until the customer has corrected the condition in conformance with the State and local statutes relating to plumbing, water supplies and the regulations adopted pursuant thereto. Water service to any premises shall be discontinued if it is found that a backflow prevention assembly has been removed, bypassed, or if an unprotected cross connection exists on the premises. Service will not be restored until such conditions or defects are corrected.

(D) "Existing Service Connections" - All existing water service connections which do not have backflow prevention assemblies or existing water service connections which have less than the minimum required backflow prevention assemblies, shall, except for the inspection requirements, be excluded from the requirements of this resolution so long as the Water District is assured that the public water system is satisfactorily protected. Whenever the existing service connection is moved or requires more than minimum maintenance or when the Water District determines that a hazard to health exists, then a backflow prevention assembly meeting the requirements of this resolution shall be installed on such existing service connection. Periodically, the Water District shall install or require to be installed backflow prevention assemblies on existing unprotected water service connections until such time that all water service connections within the public water system are equipped with backflow prevention assemblies. Backflow prevention assemblies shall not be installed on existing service connections until after the property owner of such residential or commercial property has been informed of the actual and potential hazards that may be created as a result of such backflow assembly installation. Notices provided to such property

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

APR 27 1996

PURSUANT TO 807 KAR 5011,
SECTION 9(1)

BY: Jordan C. Neal
FOR THE PUBLIC SERVICE COMMISSION

DATE OF ISSUE January 23, 1996

DATE EFFECTIVE February 23, 1996

ISSUED BY

Name of Officer, Chairman

Box 520, Elkton, KY 42220

Address

P.S.C. KY No. 8943

Original Sheet No. 28

Cancelling P.S.C. KY No.

Sheet No.

Todd County Water District


RULES AND REGULATIONS

owners shall include the following language as adopted in 815 KAR 20:120 Section 2. item (6): When cross connection control devices are properly installed, they create a closed water system. A properly sized thermal expansion tank shall be installed in the cold water supply located as near the water heater as possible.

SECTION 5. SEVERABILITY. If any provision of this resolution is deemed by a court of competent jurisdiction to be unenforceable or unconstitutional or in conflict with applicable laws of the Commonwealth, the remaining provisions of this resolution shall continue in full force and effect.

SECTION 6. EFFECTIVE DATE. This resolution shall take effect upon the incorporation into the Bylaws and PSC Tariff of the Todd County Water District.


Date of adoption 12-4-95


Dr. George D. Brown, Chairman

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE


APR 27 1996

PURSUANT TO 807 KAR 5011,
SECTION 9 (1)

BY: 
FOR THE PUBLIC SERVICE COMMISSION

DATE OF ISSUE January 23, 1996

DATE EFFECTIVE February 23, 1996

ISSUED BY  P O Box 520, Elkton, KY 42220

FOR _____

P.S.C. Ky. No. _____

Sheet No. _____

Cancelling P.S.C. Ky. No. _____

Sheet No. _____

Todd County W.D.

RULES AND REGULATIONS

TODD COUNTY WATER DISTRICT
P.O. BOX 836
ELKTON, KY 42220

ACCOUNT NO. 007-00295-00
FOR SERVICES AT

READING DATE 04/01/92 ARREARS 0

PREVIOUS READING CURRENT READING USAGE

GS
WA 0
AVG. GS WA 0

CURRENT CHARGES:
CODE AMOUNT
UT 0.36
WA 12.00

NET AMOUNT
12.36

DUE DATE
04/10/92

GROSS AMOUNT
13.56

NEW RATES IN EFFECT

CUTOFF DATE 04/25/92

TODD COUNTY WATER DISTRICT

PRESORTED U.S. POSTAGE PAID
FIRST CLASS PERMIT NO. 36
ELKTON
KY 42220

ELKTON, KY 42220

ACCT. NO. 007-00295-00
PAY GROSS AFTER 04/10/92

GROSS AMT.
13.56

NET AMT.
12.36

RETURN THIS STUB WITH PAYMENT

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

MAY 29 1992

DATE OF ISSUE 4 6 92
Month Day Year

DATE EFFECTIVE 5 6 92
PURSUANT TO 507 KAR 5.011
SECTION 9(1) Month Day Year

ISSUED BY
Name of Officer

BY: [Signature]
Title PUBLIC SERVICE COMMISSION MANAGER Address

EXISTING SERVICE CONTRACT

This contract, made and entered into this _____ day of _____, 19____, between _____ whose address is _____, party of the first part, and THE TODD COUNTY WATER DISTRICT, P O Box 836, Elkton, KY 42220, party of the second part,

WITNESSETH:

That for and in consideration of the mutual covenants and agreements of the parties hereto, and herein contained, they agree as follows:

1. First party/parties agree to purchase water from second party, and second party agrees to furnish water to first party/parties. First party/parties further agree to pay a monthly water rate based upon the amount of water used, and said rate shall be approved by the Kentucky Public Service Commission.

2. The first party/parties rights hereunder are subject to such further rules and regulations as the party of the second part may prescribe. Second party may terminate service to any customer failing to pay a water bill when fifteen (15) days past due or for violating the organization's regulations.

3. First party/parties understand that they are to pay their new water bills on or before the tenth (10th) of each month, and that a ten (10%) per cent late charge will be added for all bills not paid by the tenth of each month. It is further understood that late payments may not be reflected in the billing, and failure to receive bills will not avoid payment on the part of first party/parties. It is further agreed that all past due bills are subject to collection and for trip fee charges paid in full before service is restored, in the event the service is terminated due to failure to pay water bill within fifteen days past due, or for other violations of second party's regulations. It is further understood that first party/parties shall be required to pay all charges incurred by second party for collection of past due bills, including court costs and attorney fees, and also first party/parties shall pay a reasonable, approved reconnection fee in the event service has been terminated for lack of payment.

4. First party/parties further agree to grant, bargain, sell, transfer and convey unto second party, its successors or assigns, a perpetual easement with the right to erect, construct, install and lay, and thereafter use, operate, inspect, repair, maintain, replace and remove a water line over, across and through the lands of first party/parties situated in Todd/Logan Counties, Kentucky, and further to grant unto second party the right of ingress and egress for these purposes over first party/parties property.

5. It is further understood and agreed **PUBLIC SERVICE COMMISSION OF KENTUCKY** the water line from the meter to first party/parties' **EFFECTIVE** building served by the water line, shall be the sole responsibility of first party/parties.

6. It is understood that when first party/parties request that

water service begin for the benefit of first party/parties, they must have all valves or fixtures turned off, and second party is not responsible for water damage caused by open valves or fixtures.

7. First party/parties agree that no other present or future source of water will be connected to any water line served by the District's lines and will disconnect from their present water supply prior to connecting to and switching to the District's system, and shall eliminate their present or future cross connections in their system.

8. First party/parties agree to comply with and be bound by the articles, by laws, rules and regulations of the District, now in force, or as hereafter duly and legally supplemented, amended or changed.

9. First party/parties agree to pay a tap on fee of \$350.00, as of the date of the signing of this contract. Tap on fee collected at the signing of the contract is \$_____, with any balance to be paid in monthly installments.

IN TESTIMONY WHEREOF, witness the signatures of first and second parties hereunto subscribed the day and date first above written.

Customer Signature _____

Todd County Water District

Social Security Number _____

By: _____

STATE OF KENTUCKY

COUNTY OF TODD

The foregoing instrument was acknowledged before me this _____ day of _____, 19____, by _____ and _____ first party/parties.

**PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE**

NOTARY PUBLIC, State of KY at Large
My Commission Expires _____

JAN 2 1991

**PURSUANT TO 807 KAR 5:011,
SECTION 9(1)**

STATE OF KENTUCKY

COUNTY OF TODD

BY: [Signature]
PUBLIC SERVICE COMMISSION MANAGER

The foregoing instrument was acknowledged before me this _____ day of _____, 19____, by _____ of the Todd County Water District, second party.

NOTARY PUBLIC, State of KY at Large
My Commission Expires: _____

Todd County Water District

Post Office Box 836
Elkton, Kentucky 42220

Phone: 502-277-9048

Account Number:

Dear Customer:

Kentucky Public Service Commission Regulation 807 KAR 5:006, Section 20 states that a customer's request to test a meter must be made in writing. Such request may be made once in a twelve (12) month period. You have the opportunity to be present at such test if you desire. If the required test results is an average error of greater than 2%, the account will be adjusted for the period the meter's error is known to have existed or for one-half the period of time between the present date and the last meter test date or twelve months, whichever is less. If the average error is greater than 2% slow, the customer will receive an additional bill under the same conditions as above.

After having a test made on your meter by _____, if you are not satisfied with the results, you may make written application to the Public Service Commission to have your meter tested by the Commission. Application may be made by writing:

Commonwealth of Kentucky
Public Service Commission
730 Schenkel Lane
Post Office Box 615
Frankfort, KY 40602

Such request of the Commission may not be made more frequently than once each twelve (12) months.

If you desire a meter test by the testing facility mentioned above please sign below and return this form to our office. The meter test fee is \$7.50.

**PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE**

Signature _____

Date _____

IAN 2 1991

PURSUANT TO 807 KAR 5:011,
SECTION 9 (1)

BY: James H. Hinkle (See Reverse for Test Results)
PUBLIC SERVICE COMMISSION MANAGER

FILED

JUL 19 1988

WATER SHORTAGE RESPONSE PLAN
TODD COUNTY WATER DISTRICT

PUBLIC SERVICE
COMMISSION

Section 1. Purpose. The purpose of this plan is to provide for the declaration of official phases of water supply shortages and the implementation of voluntary and mandatory water conservation measures throughout the District in the event a shortage is declared.

Section 2. Definitions. These terms are applicable only for this Plan unless specifically noted.

- (a) "Customer" shall mean any person or entity using water for any purpose from the Todd County Water District's water distribution system and for which either a regular charge is made or, in the case of bulk sales, a cash charge is made at the site of delivery.
- (b) "Raw Water Supplies" shall mean all water potentially available to persons in the Todd County Water District.
- (c) "Treated Water" shall mean water that has been introduced by the Todd County Water District into its water distribution system, including water offered for sale. Uses of treated water are classified as follows:

Essential Water Uses (Class 1):

The following uses of water, listed by site or user type, are essential.

Domestic:

- water necessary to sustain human life and the lives of domestic pets, and to maintain minimum standards of hygiene and sanitation.

Health Care Facilities:

- patient care and rehabilitation, including related filling and operation of swimming pools.

Water Hauling:

- Sales of domestic use where not reasonably available elsewhere.

Public Use:

- firefighting
- health and public protection purposes, if specifically approved by health officials.

Socially or Economically Important Uses (Class 2):

The following uses of water, listed by site or user type, are socially or economically important.

Domestic:

- personal, in-house water use including kitchen, bathroom and laundry.

Water Hauling:

- non-domestic, when other sources are not reasonably available elsewhere.

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

JUL 20 1988

PURSUANT TO KRS 5.011,
SECTION 9 (1)

PUBLIC SERVICE COMMISSION MANAGER

Commercial and Civic Use:

- commercial car and truck washes
- laundromats
- restaurants, clubs and eating places
- schools, churches, motels/hotels, and similar commercial establishments

Outdoor Non-Commercial Watering:

- minimal watering of vegetable gardens
- minimal watering of trees where necessary to preserve them

Outdoor Commercial or Public Watering (using conservation methods and when other sources of water are not available or feasible to use):

- agricultural irrigation for the production of food and fiber or the maintenance of livestock
- watering by arboretums and public gardens of national, state, regional or community significance where necessary to preserve specimens
- watering by commercial nurseries at a minimum level necessary to maintain stock
- watering at a minimum rate necessary to establish or maintain revegetation or landscape planting required pursuant to law or regulation
- watering of woody plants where necessary to preserve them
- minimal watering of golf course greens

Recreational:

- operation of municipal swimming pools and residential pools that serve more than 25 dwelling units

Air Conditioning:

- refilling for startup at the beginning of the cooling season
- makeup of water during the cooling season
- refilling specifically approved by health officials where the system has been drained for health protection or repair services

Non-Essential Uses (Class 3):

Any waste of water, as defined herein, is non-essential. The following uses of water, listed by site or user type, are non-essential.

Public Use:

- use of fire hydrants (excluding Class 1 and Class 2 uses), including use of sprinkler caps, testing fire apparatus and fire department drills
- flushing of sewers and hydrants except as needed to ensure public health and safety as approved by health officials

Commercial and Civic Use:

- serving water in restaurants, clubs, or eating places, except by customer request

PUBLIC SERVICE COMMISSION
OF KENTUCKY

EFFECTIVE

JUL 20 1988

SECTION 9.01

BY: *[Signature]*
PUBLIC SERVICE COMMISSION MANAGER

- failure to repair a controllable leak
- increasing water levels in scenic and recreational ponds and lakes, except for the minimum amount required to support fish and wildlife

Ornamental Purposes:

- fountains, reflecting pools and artificial waterfalls

Outdoor Non-Commercial Watering:

- use of water for dirt control or compaction
- watering of annual or non-woody plants, lawns, parks, golf course fairways, playing fields and other recreational areas
- washing sidewalks, walkways, driveways, parking lots, tennis courts, or other hard-surface areas
- washing down buildings or structures for purposes other than immediate fire protection
- flushing gutters or permitting water to run or accumulate in any gutter or street

Outdoor Commercial or Public Watering:

- expanding nursery facilities, placing new irrigated agricultural land in production, or planting of landscaping except when required by a site design review process
- use of water for dirt control or compaction
- watering of lawns, parks, golf course fairways, playing fields, and other recreational areas
- washing sidewalks, walkways, driveways, parking lots, tennis courts, or other hard-surface areas
- washing down buildings or structures for purposes other than immediate fire protection
- flushing gutters or permitting water to run or accumulate in any gutter or street

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

Recreational uses other than those specified in Class 2.

Non-commercial washing of motor and other vehicles.

Air Conditioning (see also Class 2 purposes).

- refilling cooling towers after draining

- BY: *[Signature]*
PUBLIC SERVICE COMMISSION MANAGER
- (d) "Base Entitlement" shall mean the monthly usage for a customer during the same month of the preceding calendar year or the average per customer usage for each class of service during the same month of the preceding year.
- (e) "Curtailed Entitlement" shall mean the monthly usage for a customer after any curtailment percentage has been applied.
- (f) "Curtailment" shall mean the reduction in entitlement by some percentage to meet anticipated water shortages.

(g) Water Shortage Response Phases:

"Advisory" shall mean that conditions exist which indicate the potential for serious raw or treated water supply shortages.

"Alert" shall mean the raw or treated water supplies are consistently below seasonal averages, and if they continue to decline, may not be adequate to meet normal needs.

"Emergency" shall mean that raw or treated water supplies are below the level necessary to meet normal needs and that serious shortages exist in the area.

- (h) "Rationing" shall mean that procedures must be established to provide for the equitable distribution of critically-limited raw or treated water supplies, in order to balance demand and limited available supplies, and to assure that sufficient water is available to preserve public health and safety.

Section 3. Applicability. The provisions of this Plan shall apply to all retail and wholesale customers of the Todd County Water District. When implemented, this Plan becomes Todd County Water District's Water Shortage Response Regulation.

Section 4. Entitlements. Entitlements shall be established for each customer by adjusting the base entitlements to reflect any known change in usage pattern.

Section 5. Determination of Water Shortage. Water supply and usage shall be monitored on a continuous basis. Unrestricted demand shall be projected from past records and adjusted for changes such as new developments and weather conditions on a regular basis. (Note: A sample calculation page is attached as Appendix A to assist in determining overall water levels. It is important that accurate water measurements be used.) Water shortages generally occur for two reasons, a reduction in available supplies or a system failure. Each of these has a distinct influence on the nature and duration of the conservation program implemented. Official declaration of a water shortage stage and implementation of the measures necessary to curtail water use shall be approved by the Todd County Water District Board of Commissioners.

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE
JUL 20 1988
PURSUANT TO 807 KAR 5-011
SECTION 9(1)
BY: [Signature]
PUBLIC SERVICE COMMISSION MANAGER

Section 6. Term of Water Shortage Declaration. Any water shortage declaration shall remain in effect until water supplies of service conditions have returned to normal. A final determination as to terminating a water shortage declaration shall be made by the Superintendent of Todd County Water District.

Section 7. Water Shortage Stage, Criteria, Conservation and Curtailment Measures.

A. Advisory Stage:

(1) Criteria: A water advisory shall be declared when the amount of treated water or raw water available for treatment is projected to be up to 10% below demand, or there are periods of low water pressure in one or more areas of the distribution system due to system failure or inadequacies or the State Division of Water issues a Water Shortage Watch which includes the areas from which the District draws water.

(2) Conservation and Curtailment Measures:

(a) Declare a Water Shortage Advisory.

(b) Provide proper notice to all customers and to all local news media.

(c) Eliminate all water leaks.

(d) Request voluntary conservation of all non-essential (Class 3) water use.

B. Alert Stage:

(1) Criteria: A water alert shall be declared when the amount of treated water available is projected to be up to 25% below demand, or raw water supplies are consistently below seasonal averages and if they continue to decline, may not be adequate to meet normal needs.

(2) Conservation and Curtailment Measures:

(a) Declare Water Shortage Alert.

(b) Provide proper notice to all customers and to all local news media.

(c) Eliminate all water leaks.

(d) Prohibit all non-essential (Class 3) water uses.

(e) Curtail entitlements to all customers by the same percentage as the projected shortage.

(f) Begin billing all customer water usage in excess of curtailed entitlement at the normal rate plus an excess usage charge of \$15.00 per 1,000 gallons.

C. Emergency Stage:

(1) Criteria: A Water Emergency shall be declared when the amount of treated water available is projected to be up to 30% below demand, or there are periods of no water in one or more areas of the distribution system due to low water supply or raw water supplies below the level necessary to meet normal needs.

(2) Conservation and Curtailment Measures:

(a) Declare Water Shortage Emergency.

(b) Provide proper notice to all customers and to all local news media.

(c) Eliminate all water leaks.

(d) Prohibit all Class 3 uses of water.

(e) Prohibit all Class 2 uses of water except Domestic uses for kitchens, bathrooms and laundries.

(f) Curtail all commercial and industrial entitlements (except Health Care Facilities) by 100%.

- (g) Curtail Residential entitlements by the same percentage as the projected shortage.
- (h) Curtail entitlements to all wholesale customers by the same percentage as the projected shortage.
- (i) Begin billing all customer water usage in excess of curtailed entitlement at the normal rate plus an excess usage charge of \$15.00 per 1,000 gallons.

D. Rationing Stage:

- 1. Criteria: Treated water available is greater than 50% below demand or raw water supplies are below the level necessary to meet essential needs, and in the opinion of the Water Superintendent, mandatory rationing is required to insure adequate water is available to maintain public health and safety.
- (2) Conservation and Curtailment Measures:
 - (a) Declare Water Shortage Rationing.
 - (b) Provide proper notice to all customers and to all local news media.
 - (c) Eliminate all water leaks.
 - (d) Prohibit all Class 3 and Class 2 uses of water.
 - (e) Curtail all commercial and industrial entitlement (except Health Care Facilities) by 100%.
 - (f) Curtail all residential and wholesale entitlements by the same percentage as the projected shortage.
 - (g) Implement service interruptions to portions of system in accordance with approved published schedule. The schedule shall be provided to all local media.
 - (h) Begin billing customer water usage in excess of curtailment entitlement at the normal rate plus an excess usage charge of \$15.00 per 1,000 gallons.

Section 8. Enforcement of Water Restriction. Any person who violates the provisions of this Plan, who fails to carry out the duties and responsibilities imposed by this Plan, or who impedes or interferes with any action undertaken or ordered pursuant to this Plan shall be subject to the following:

- (a) If the utility official charged with implementation and enforcement of this Plan learns of any violation of any water use restriction imposed, a written notice of the violation shall be affixed to the property where the violation occurred and mailed to the customer of record. Said notice shall describe the violation and order that it be corrected, cured, or abated immediately or within 48 hours.
- (b) The notice will inform the customer of his or her right to appeal by requesting a hearing before the utility's designee. If a hearing is requested by the customer, he or she shall be given full opportunity to be heard before termination. The governing body shall make findings of fact and decide whether service should continue or terminate.

- (c) Any customer whose water service is terminated for violating provisions of this water curtailment plan shall be subject to the approved reconnection fee prior to reconnection of service.
- (d) The excess usage charge billing provisions of this Plan shall not be put in effect if a county or city ordinance containing penalty provisions is in effect to assist enforcement of this Plan.

Section 9. Request for Exception.

- (a) Exception to water use restrictions: If compliance with any curtailment measure authorized herein would cause a customer to bear extraordinary hardship, that individual or entity may apply to the Water District for an exception. For these purposes, "extraordinary hardship" shall be defined as a condition which may threaten health and safety, or cause property or economic losses, each of which must be shown to be substantially more severe than the sacrifices borne by other users. If extraordinary hardship is found to exist, then an exception shall be granted and a written waiver issued to the customer. If an appeal is made, water service shall be continued until a decision is announced. Any person aggrieved by the decision may file a complaint with the Public Service Commission.
- (b) Exception to curtailment surcharge: Exceptions to excess use charges shall not be considered or granted.

Section 10. Severability. If any provision of this Plan is declared invalid by the courts, the remainder of the Plan and its applicability to other persons and circumstances shall not be affected by that declaration.

Section 11. Effective Date. This Plan shall take effect immediately upon approval by the Public Service Commission.

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

JUL 20 1988

PURSUANT TO 807 KAR 5:011,
SECTION 9 (1)
BY: [Signature]
PUBLIC SERVICE COMMISSION MANAGER

APPENDIX A

TODD COUNTY WATER DISTRICT

PROJECTED DEMAND WORKSHEET FOR _____ (Month) (Year)

The information below would be used to estimate projected demand for one (1) month.

Calculations will be done at the beginning of each month.

Average use in _____ for the past 5 years: _____ gpd
(Last Month)
Average use in _____ for 2 years ago: _____ gpd
(Last Month)
Average use in _____ for 1 year ago: _____ gpd
(Last Month)
Average use in _____ for current year: _____ gpd
(Last Month)
Average use in _____ for the past 5 years: _____ gpd
(This Month)
Average use in _____ for 2 years ago: _____ gpd
(This Month)
Average use in _____ for 1 year ago: _____ gpd
(This Month)

Usage Notes: _____

Weather Notes: _____

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

JUL 20 1988

PURSUANT TO 807 KAR 5:011,
SECTION 2.11

BY: *[Signature]*
PUBLIC SERVICE COMMISSION MANAGER

Average projected use for _____
Without conservation measures: _____ gpd
With advisory conservation measures
(reduction) _____ gpd
With alert conservation measures
(More than reduction) _____ gpd
With emergency conservation measures
(More than reduction) _____ gpd
With rationing conservation measures
(More than reduction) _____ gpd